

HLP SITE CONSTRUCTION/INSTALLATION CHECKLIST

(LAST REVISION 9/26/07 DEJ)

I. BUILD VAULT

- A. lay out site (solar panels facing south, and downhill of vault)
- B. dig hole for vault and action packer and trench between
- C. 2 bags of concrete in hole
- D. set barrel and level
- E. 1 bag of concrete in vault and trowel flat

II. SOLAR PANELS

- A. trench 8-10 ft to solar
- B. drive two 6' steel posts for solar panel
- C. construct solar mounts
 1. drill holes in Carlson frames and pull rebar through
 2. mount solar panels using wire ties and bolt panels together
 3. mount GPS on reduced (1 ½") section

III. LAY PIPING

- A. cut and dry fit
- B. run wire (GPS and solar)
- C. Prime and glue PVC from solar to T

IV. INSTRUMENT & DAS (in tandem) [*Follow Q330 or RT130 install sheet*]

- A. Instrument
 1. vault documentation (to be written on vault floor):
 - a. 'N' arrow
 - b. station name
 - c. declination
 2. align, level, lock feet, and burp (Guralp only) instrument, and unlock masses (Streckeisen and Guralp ESP only)
- B. DAS
 1. connect batteries & solar to power box
 2. connect GPS & power to DAS
 3. start station log sheet -> program DAS
- C. connect instrument (& HCU for Guralps) -> check instrument
 1. Guralp (using HCU):
 - a. lock masses
 - b. unlock masses: check to see they unlock and center
 - c. re-lock masses
 2. Streckeisen
 - a. check masses
 - b. center masses
 - c. monitor channels

V. FINISH VAULT

- A. install hut & RPBs (don't forget cork)
- B. close lid vault
- C. check instrument
- D. bury vault and pipes
- E. start acquisition
- F. cork GPS/solar and DAS
- G. cover action packer with tarp and rocks

VI. BUILD FENCE:

- A. Four braced corner posts (8 6' steel posts)
- B. Run three-strand barbed wire
- C. Two intermediate posts to tighten barbed wire